

APPROVED BY PEER GROUP  
 P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT  
 SAGINAW COUNTY LIBER 1925 PAGE 331

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

*Lib 6 Page 257*

For corners in

Saginaw (County) SURVEY & Located In:

Corner Code #

REMONUMENTATION

- |                                   |                |               |            |
|-----------------------------------|----------------|---------------|------------|
| 1. Public Land Survey             | T <u>12 N.</u> | R <u>3 E.</u> | <u>M-3</u> |
|                                   | T _____        | R _____       | _____      |
|                                   | T _____        | R _____       | _____      |
|                                   | T _____        | R _____       | _____      |
| 2. Property Contained in Section  | S _____        | T _____       | R _____    |
| 3. Miscellaneous Property in Sec. | S _____        | T _____       | R _____    |

APR 24 1995

COMMISSION

RECORDED & FILED  
 DEC 27 9 15 AM '94  
 MICHIGAN BOARD OF LAND SURVEYORS  
 REGISTER OF DEEDS  
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-3 Post by Wampler in 1822.  
 Bccch 11" N.62°W. 17 Lks.  
 Sugar 18" N.84°E. 13 Lks.  
 LCRC L.4, P.165 Hammond 1978 3/4" Pipe  
 Recorded Survey L.1664, P.307 Prevost, 1985, 3/4" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-3 Found 3/4" Pipe & Recorded Witnesses  
 S.45°W. 57.70 top hydrant (S.60°W 57.77 center hydrant)  
 South 20.46 NW corner Sec. 7, T.12 N.-R.4 E. (S.20.00 corner A-3, T.12 N.-R.4 E.)

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3 Replaced 3/4" Pipe with 5/8" Rerod 2 1/2" Saginaw Co. Bronze Cap & Mon. Box  
 S.40°W. 63.58 Nail in E. Face P Pole  
 S.60°W. 57.77 center hydrant  
 N.45°W. 46.28  
 S.50°E. 82.75 Nail in SW Face P & T Pole  
 South 20.00 Corner A-3, T.12 N.-R.4 E.



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612