

12-7-94 [Signature]

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Sheet 6 Page 255

For corners in

Saginaw
 (County)

**SURVEY &
 REMONUMENTATION**

Located In:

Corner Code =#

1. Public Land Survey T 12 N. R 3 E. M-5
 APR 24 1995
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Cornering in Section S _____ T _____ R _____
 S _____ T _____ R _____
3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

COMMISSION

MICHIGAN
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

DEC 27 9 15 AM '94

RECORDED & FILED

Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-5 Post by Joseph Wampler in 1822.
- M-5 LCRC L.3, P.229 Martin 3/4" Bar, 1976
 Corner A-5, T.12 N.-R.4E., recorded in LCRC L.4, P.73, By Martin 1977 uses same witnesses as M-5, L.3, P.229
 Corner A-5, T.12 N.-R.4 E., recorded in 1993 Remon Prevost, L.1890, P.771 & ratified by Peer Group on 12-22-93 with following note: Corner A-5, T.12 N.-R.4 E, has been used as a common corner with M-5, T.12 N.-R.3 E., since about 1925 even though A-5 should be 13.2 feet South of M-5
 Plats Alma Court & Young's Subdivision in Sec 18, T.12 N.-R.4 E., are tied into corner. Reinke Plat is Sec 13, T.12 N.-R.2 E., is tied into same point.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-5 Found 5/8" Rebar with Saginaw Co. Remon Bronze Cap in Mon. Box from 1993 Remon project (as T.12 N.-R.4 E.)

 Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5 5/8" Rebar with Saginaw Co. Remon Bronze Cap in Mon. Box
 Center M.H. cover N.70°E 36.42
 Nail & Cap NW face P & T Pole S.60°E. 57.54
 Hydrant S.65°E. 66.81
 Nail & Cap S Face P & T Pole S.45°W. 37.90
 Nail & Cap NE Face P & T Pole N.60°W. 66.52
 Same point as A-5, T.12 N.-R.4 E.



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612