

APPROVED BY PEER GROUP P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT

RECORDED & FILED  
DEC 27 9 15 AM '94  
MILLET W. GODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SURVEY & REMONUMENTATION

- 1. Public Land Survey Commission APR 24 1995 T 12 N. R 3 E. M-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Sheet 6 Page 251  
Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (6,13) contains a dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-6 Post set by Joseph Wampler, 1822
Sugar 34" S.30°W. 26 Lks.
Sugar 14" N.9°W. 14 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Note: Corners M-7, T.12 N.-R.3 E., and A-7, T.12 N.-R.4 E., are a common corner by Government Notes. Corner A-5, T.12 N.-R.4 E., was recorded in L.1890, P.771, Saginaw Co. 1993 Remon Project and Corner M-5, T.12 N.-R.3 E., is being recorded in the Saginaw Co. 1994 Remon Project as a common point by use since about 1925 when a point was set by Redmond. Corner A-6 was recorded in L.1890, P.777, 1993, Saginaw Co. Remon Project. No evidence of M-6, T.12 N.-R.3 E., being different than A-6, T.12 N.-R.4 E., could be found; no surveys, descriptions, drawings or any other evidence could be found that would indicate two corners.

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6 Found 5/8" Rebar with Saginaw Co. Bronze Cap & Mon. Box
Center manhole cover N.70°E. 36.42
Nail & Cap NW Face P & T Pole S.60°E. 66.81
Hydrant S.65°E. 57.54
Nail & Cap S Face P & T Pole S.45°W. 37.90
Nail & Cap NE Face P & T Pole N.60°W. 66.52
Same Point as A-6, T.12 N.-R.4 E.



Signed by [Signature] Date 12-15-94

Surveyor's Michigan License No. 24612