

SAGINAW COUNTY REMONUMENTATION

DEC 15 1993

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
RECORDED & FILED

For corners in  
Saginaw  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 12 N. R 4 E. A-4  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

DEC 9 4 27 PM '93

MILDRED E. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

*Liber 1887 Page 1017*  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	10	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ronald C. Prevost, in a field survey on Oct./Dec., 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- A-4 Not Set During Gov't. Survey  
Co. Surveyor H. Cary, 1878, stakes and stones buried.  
Charles Redmond Notes, 1925, 3 stones together 6" below surface.  
Set 3/4" pipe to better mark the point, SE to NW cor. conc Hdw'l 39.8.  
SW to NE Cor. Conc. Hdw'l 39.9  
NW to SW Cor. Conc. Hdw'l 17.2  
NE to SW Cor. Conc. Hdw'l 11.0  
Spicer notes 1950 set 3/4" pipe according to Redmond's witnesses.  
Pipe is at end of old conc. pv't @ centerline joint.  
SW 38.96 to NW cor. of W. conc. hdw'l. of culvert  
SE 39.74 to NW cor. of E. conc. hdw'l. of culvert


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-4 Found 3/4" Pipe @ Bit. Surface and is accepted as: This position not established by original government surveyors. The monument is accepted as the best available evidence of the position of the corner.

Ratified by Saginaw County Peer Review Group 9-23-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-4 Set 5/8" x 18" Re-bar with Saginaw Co. Re-mon Bronze Cap Stamped #24612 & Mon. Box in place of 3/4" pipe.  
SW Cor. R.R. Rail N.15°E. 35.06  
Nail & Cap NW Cor. Guard Rail Post N.86°E. 12.53  
Nail & Cap NE Cor. Guard Rail Post N.85°W. 19.81  
Nail & Cap NE Cor. Guard Rail Post N.20°W. 46.13  
Hyd. N.15°W. 116.43



Signed by *Ronald C. Prevost*

Date 12-9-93

Surveyor's Michigan License No. 24612