

NOV 12 1993

LIBER 1882 PAGE 1664

*Libert Page 118*

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Saginaw  
(County)

Located In:

Corner Code #

	12N	4E	A-8
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

RECEIVED & FILED  
 NOV 3 12 31 PM '93  
 HILPOSS & SODAK  
 REGISTER OF DEEDS  
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John H. Rauser, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-8 Closing 1/4 cor., Sec. 19, T12N-R4E  
 Not set by original government survey.  
 No record of subsequent determination.


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-8 Closing 1/4 cor., Sec. 19, T12N-R4E  
 Fnd. no evidence of existing corner. Using method as described in the 1973 BLM Manual of Instructions the corner was placed midway between the closing corners at A-7 & A-9 on the township line between M-7 & M-9.

Approved by Saginaw County Peer Review October 7, 1993

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-8 Closing 1/4 cor., Sec. 19, T12N-R4E  
 Set 5/8" re-rod w/brass cap stamped Saginaw County Monument, P.S. #39096 in CP Co. easement. This position not established by original government survey. This monument is accepted as a careful and faithful determination of the position of the corner.  
 S12 E 33.02' 1" nut welded to West base of transmission tower  
 N89 W 98.08' Set spike w/tag #12018 in N face 8" Ash  
 S68 W 79.33' Set spike w/tag #12018 in NW face 8" Ash  
 N48 W 111.81' Set spike w/tag #12018 in NE face 12" Twin Ash



Signed by John H. Rauser Date 11/03/93  
 Surveyor's Michigan License No. 39096

*11/18/93*