

SURVEY & REMONUMENTATION

LIBER 1889 PAGE 201
1993

LAND CORNER RECORDATION CERTIFICATE
COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>12</u> N. S., R. <u>4</u> E. W.	<u>A-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

RECORDED & FILED
Liber 6 Page 171
DEC 22 2 12 PM '93
MICHIGAN REGISTER OF DEEDS
SAGINAW COUNTY MICH.
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Duane F. Ledy, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on September, 1993, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

In 1822, Wampler intersected standard line 5 links South of M-11 post at 71.24 chains. Stephen Soltis, Jr. set P.K. nail as corner A-11 5 links South of found corner M-11, T12N, R3E on Oct. 27, 1972, recorded in L2, P133; Leach used corner on survey dated Dec. 19, 1974, recorded in L1438, P249.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found R.R. spike 3.30 South of corner M-11. Existing corner accepted by usage and approval by Saginaw County Remonumentation Peer Group Review Meeting on Oct. 7, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" Rod & Sag. Co. Remon. 3" Brass Cap in monument box.

N 87 W	31.92	Nail & brass tag marked "P.S. 21575" in E. side util. pole
North	3.30	Rod in monument box; corner M-11 T12N, R3E
N 20 E	75.88	Nail & brass tag marked "P.S. 21575" inside 10" box elder
East	41.78	Nail & brass tag marked "P.S. 21575" in S. side power pole
S 35 W	47.84	Top center of hydrant
West	0.05	To standard line


SIGNED BY Duane F. Ledy DATE Dec 22 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 21575

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____