

1993 LAND CORNER RECORDATION CERTIFICATE  
COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

| FOR CORNERS OF--:                          | LOCATED IN--:                         | CORNER CODE NUMBER |
|--|---------------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. <u>12</u> N. S., R. <u>4</u> E. W. | <u>A-13</u>        |
| 2. PROPERTY CONTROLLING IN SECTION _____   | T. _____ N. S., R. _____ E. W.        | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S., R. _____ E. W.        | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____      |                                       |                    |
| 5. PRIVATE CLAIMS _____                    |                                       |                    |

RECORDED & FILED  
*Liber 6 page 173*  
DEC 22 2 12 PM '93  
MICHIGAN STATE BOARD OF REGISTRATION  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.  
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Duane F. Ledy, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on September, 1993, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
Temporary post set in 1822 by J. Wampler at a standard corner common to T11N and T12N and R3E and R4E 80.00 chains from C-13. True corner subsequently established at 71.10 in 1822.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
Found R.R. spike at ineresection; existing corner monument accepted by usage for surveys and subdivisions in the area. Approval by Saginaw County Remonumentation Peer Group on September 30, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 5/8" rod & Sag. Co. Remon. 3" brass cap in monument box.

- N 30 E 92.28 Nail and brass tag marked "P.S. 21575" in NW face power pole
- N 35 W 53.78 Nail and brass tag marked "P.S. 21575" in W. face power pole
- S 60 W 90.47 Nail and brass tag marked "P.S. 21575" in N. face power pole
- S 80 E 35.07 Nail and brass tag marked "P.S. 21575" in S. face power pole
- S 30 E 64.72 Top center of hydrant

SIGNED BY Duane F. Ledy DATE Dec. 22, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 21575

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_