

**SURVEY & REMONUMENTATION**

LIBER 1882 PAGE 1665

*Liber 6 Page 11*

NOV 12 1993

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Saginaw

	Located in:		Corner Code #
	12N	4E	
1. Public Land Survey	T _____ R _____	_____	B-9
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

REGISTERED & FILED  
 NOV 3 12 32 PM '93  
 HILGARD L. DODAK  
 REGISTER OF DEEDS  
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9	•											
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John H. Rauser, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

B-9 1/4 cor., Sec. 19 & 30, T12N-R4E

Wood post placed by J. Wampler, 1822  
 N67°E 11 lks. (7.26') 12" Ash  
 S37°E 22 lks. (14.52') 18" Lynnwood  
 No record of subsequent restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B-9 1/4 cor., Sec. 19 & 30, T12N-R4E

Fnd. no evidence of original government corner.  
 Set corner at a proportional position to GLO measurement on line between Sec. cor., 19, 20, 29 & 30, and Closing cor., Secs. 19 & 30.

Approved by Saginaw County Peer Review October 7, 1993

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B-9 1/4 cor., Sec. 19 & 30, T12N-R4E

Set 5/8" re-rod w/brass cap stamped Saginaw County Monument, P.S. #39096 and is accepted as the best available evidence of the position of the original corner.  
 S56°W 1.42' Set spike w/tag #12018 S face 4" Walnut  
 S80°E 16.76' Set spike w/tag #12018 NNE face 12" Twin Chinese Elm  
 S43°E 46.41' Fnd. 3/4" pipe #24612  
 S35°E 29.76' Set spike w/tag #12018 E face 5" Walnut



Signed by John H. Rauser  
 Surveyor's Michigan License No. 39096

Date 11/03/93

*11/18/93*