

DEC 15 1993

SAGINAW COUNTY REMONUMENTATION

Nov 24 2 02 PM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MICHAEL J. LEBDAR  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

For corners in  
Saginaw  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 12 N. R 4 E. C-3  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Liber 6 Page 142

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ronald C. Prevost, in a field survey on Oct./Nov., 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-3 Post Set by J. Wampler in 1822.  
Corner Common to Sec's. 5, 6, 7 & 8, Stone Buried in Road  
Co. Surveyor H. Cary, 1879  
3/4" Pipe Set by Spicer Eng. Crew, 1954  
NW 130.75 SE Cor. Brick House  
SW 54.24 Face 15" Hickory  
NE 52.00 Face P. Pole  
SE 64.25 Face 26" Elm

C-3 3/4" Pipe Rec'd 1971, Liber 1, Pg.49  
S.45°W. 36.5  
S.50°E. 42.35 Top Fire Plug  
N.35°W. 46.75 Spike S. Base P. Pole  
3/4" Pipe Sag. Co. Rd. Comm. 1976 (Agree)  
Recorded Surveys: L 1578 Pg 2122,  
L 1614 Pg 2022, L 1612 Pg 1980,  
L 1542 Pg 254, L 1340 Pg 622 (All Agree)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-3 Found 3/4" Pipe in Mon. Box, and is accepted as the best available evidence of the position of the original corner.

Ratified by Saginaw County Peer Review Group 9-30-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3 Set 5/8" x 18" Re-bar with Saginaw Co. Re-Mon Bronze Cap Stamped #24612 in Ex. Mon. Box  
Nail & Cap in W Face 10" Scotch Pine N.20°E. 65.55  
Nail & Cap in N Face P. & T. Pole S.35°E. 49.50  
Ctr. Hydrant S.45°E. 42.29  
Nail & Cap in NE Face 28" Shagbark Hickory S.45°W. 54.04  
Nail & cap in E Face T. Pole N.35°W. 46.78

Signed by Ronald C. Prevost  
Surveyor's Michigan License No. 24612

Date 11-24-93

