

**SURVEY & REMONUMENTATION**

NOV 12 1993

LIBER 1882 PAGE 1672

*Liber 6 Page 126*

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Saginaw

(County)

Located In:

Corner Code #

	12N	4E	C-8
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

MILUSTON A. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

NOV 3 12 32 PM '93

RECORDED & FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John H. Rauser, in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C-8 1/4 cor., Sec. 19 & 20, T12N-R4E

Wood post placed by J. Wampler in 1822  
N25°W 30 lks. (19.8') 16" Ash  
S25°E 34 1/2 lks. (22.77') 14" Hickory

1989 LCRC by B.D. Ferguson recorded in  
L. 6, pg. 53, S.C.R.

1971 recorded Plat of Amanda Subdivision  
Plat L. 19, pg. 15 & 16, S.C.R.

1992 LCRC by B.D. Ferguson recorded in  
L. 6, pg. 89, S.C.R.

1976 LCRC by John W. Martin recorded in  
L. 3, pg. 175, S.C.R.

Set 3/4" pipe from plat monument  
East 48.00' Center monument  
West 48.00' Center monument  
S45°W 121.10' NE cor. brick house  
S40°E 125.14' NW cor. brick house

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C-8 1/4 cor., Sec. 19 & 20, T12N-R4E

Fnd. 3/4" pipe at North end asph. road  
per recorded LCRC's L. 3, pg. 175, S.C.R.,  
L. 6, pg. 53, S.C.R., L. 6, pg. 89, S.C.R.  
Fnd. no evidence of original government corner

Approved by Saginaw County Peer Review September 23, 1993

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-8 1/4 cor., Sec. 19 & 20, T12N-R4E

Re-set 5/8" re-rod w/brass cap stamped Saginaw County  
Monument P.S. #39096 1'± North of North end asph. on  
centerline of Lawdale extended North and centerline of  
fence brush row to North and is accepted as the best  
available evidence of the position of the original corner.  
West 24.76' (R = 24.67') Fnd. chis. "+" in top of conc. curb  
N60°W 85.11' (R = 85.18') SE cor. brick facing of dwelling  
#6017 Amanda  
S45°E 37.85' (R = 37.85') Fnd. chis. "+" in top of conc. curb  
West 48'± (R = 48.00') Fnd. conc. mon. broken and in poor condition  
S45°W 121.10' NE cor. brick dwelling #6014 Thistle



Signed by John H. Rauser Date 11/03/93

Surveyor's Michigan License No. 39096

*11/18/93*