

SURVEY & REMONUMENTATION

NOV 12 1993

LIBER 1882 PAGE 1669

Liber 6 Page 123

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED & FILED
NOV 3 12 32 PM '93
MILDRAGE H. DODD, JR.
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

For corners in
Saginaw

Located In: Corner Code #

- | | | | | |
|------------------------------------|---|-------|----|-------|
| | | 12N | 4E | C-9 |
| 1. Public Land Survey | T | _____ | R | _____ |
| | T | _____ | R | _____ |
| | T | _____ | R | _____ |
| | T | _____ | R | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ |
| | S | _____ | T | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ |
| | S | _____ | T | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John H. Rauser, in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-9 Sec. cor., Sec. 19, 20, 29 & 30, T12N-R4E

Wood post placed by J. Wampler in 1822
N80°E 6 lks. (3.96') 5" Beech
S47°W 4 1/2 lks. (2.97') 9" Beech

1982 Act 132 survey & LCRC by Beryl M. Jones
recorded in L. 1610, pg. 2112 of survey
and L. 6, pg. 35, S.C.R.

1979 LCRC by Ronald C. Prevost recorded
in L. 4, pg. 237, S.C.R.
Fnd. 3/4" pipe per Oakwood cemetery map
S10°W 39.40' 30" Oak
S88°E 21.75' 10" Hickory
S70°W 25.30' 30" Oak
S87°W 50.60' 36" Oak
South 7.41' 12' Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 Sec. cor., Sec. 19, 20, 29 & 30, T12N-R4E

Fnd. 3/4" iron pipe as per records recorded in
L. 4, pg. 237, L. 6, pg. 35, L. 1610, Pg. 2112,
S.C.R.
Fnd. no evidence of original government corner.

Approved by Saginaw County Peer Review September 23, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Sec. cor., Sec. 19, 20, 29 & 30, T12N-R4E

Re-set 5/8" re-rod w/brass cap stamped Saginaw County
Monument P.S. #39096 at intersection of old fence East
West and South and is accepted as the best available
evidence of the position of the original corner.
South 7.91' MDOT tag in W face 14" Oak (R = 7.41 to face)
S70°W 26.51' MDOT tag in SSE face 30" Oak (R = 25.3 to face)
East 22.35' MDOT tag in S face 10" Ash (R = S88°E 21.75 to face 10" Hickory)
S87°W 19.28' MDOT tag in S face 5" Maple



Signed by John H. Rauser Date 11/03/93
Surveyor's Michigan License No. 39096

11/3/93