

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

COMMISSION

RECORDED & FILED
Liber 6 Page 176
DEC 22 2 12 PM '93
REGISTER OF DEEDS STAMP AND FILING NUMBER

Table with 3 columns: FOR CORNERS OF--, LOCATED IN--, CORNER CODE NUMBER. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section, Lot No., and Private Claims.

I, Duane F. Ledy, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on September, 1993, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration: Wood post set in 1822 by Wampler at 40.00 chains.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: Find 1/8" rod in monument box. Corner accepted by common useage by Saginaw County Remonumentation Peer Group review on September 30, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set 5/8" rod & Sag. Co. Remon. 3" brass cap. N 15 W 79.35 Nail and brass tag marked "P.S. 21575" in E. side 36" Maple N 45 W 38.14 Nail and brass tag marked "P.S. 21575" in E. side util. pole S 45 E 55.51 Nail and brass tag marked "P.S. 21575" in N. side power pole S 35 W 57.18 Nail and brass tag marked "P.S. 21575" in N. side power pole N 55 W 72.95 Top center of hydrant


SIGNED BY Duane F. Ledy DATE Dec. 22 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 21575

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE



SURVEYOR'S MICHIGAN REGISTRATION NO.