

1993 LAND CORNER RECORDATION CERTIFICATE COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY T. 12 N. S., R. 4 E. W. C-11
2. PROPERTY CONTROLLING IN SECTION T. N. S., R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION T. N. S., R. E. W.
4. LOT NO., RECORDED PLAT
5. PRIVATE CLAIMS

RECORDED & FILED Liber 6 Page 177 Dec 22 2 13 PM '93 REGISTER OF DEEDS SAGINAW COUNTY MICH. REGISTER OF DEEDS STAMP AND FILING NUMBER


I, Duane F. Ledy, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on September, 1993, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration: Wood post set in 8122 by Wampler common to Sections 29, 30, 31 and 32 at 80.00 chains. No records available of the placement of existing monumentation at C-11.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: Found 5/8" bar in monument box. Corner of record for River Forest Subdivision, recorded in Nov., 1955 and various surveys of record in area. Corner ratified by Saginaw County Remonumentation Peer Group Review on September 30, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set 5/8" rod and Sag. Co. Remon. 3" brass cap. East 43.00 Concrete monument; NW corner River Forest Subdivision East 26.27 Nail and brass tag marked "P.S. 21575" in N. side power pole S 35 W 89.58 Nail and brass tag marked "P.S. 21575" in E. side 24" Twin Ash N 20 W 114.36 Nail and brass tag marked "P.S. 21575" in W. side util. pole N 20 E 113.82 Nail and brass tag marked "P.S. 21575" in E. side poer pole

SIGNED BY Duane F. Ledy DATE Dec. 22 1993 SURVEYOR'S MICHIGAN REGISTRATION NO. 21575



FOR STATE AND UNITED STATES AGENCIES: SIGNED BY CHIEF OF SURVEY PARTY DATE APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.