

DEC 15 1993

SAGINAW COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 24 2 02 PM '93

REGISTER OF DEEDS
SAGINAW COUNTY MICH.

For corners in
Saginaw
(County)

Located In: Corner Code #

- 1. Public Land Survey T 12 N. R 4 E. D-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Liber 6 Page 145

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Ronald C. Prevost, in a field survey on Oct./Nov., 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 Corner Not Set During Government Survey
Large Pointed Stone Found by Spicer Eng. 1953

Saginaw Co. Rd. Comm., 1973 Witnessed R.R. Spike
N. 5°W. 53.5 Nail & Cap W. Side P. Pole
S. 60°E. 193.15 NW Cor. House Foundation
West 14.37 Corner D-13, T.13 N.-R.4 E.
N. 65°W. 151.59 Nail & Cap in SW Side P. Pole

D-1 Boat Spike in Mon. Box Rec'd Liber 5,
Pg. 41, 1979

West 14.42 to Mon. Box S. 1/4 Cor. Sec. 32,
T.13 N.-R.4 E.
N. 15°E. 33.45 Face 8" Pine
N. 20°W. 55.91 Nail & Cap E. Face P. Pole
South 9.45 S. Edge Bit. Road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Found 1/2" Boat Spike in Mon. Box, and is accepted as: This position not established by original government surveyors. The monument is accepted as the best available evidence of the position of the corner.

Ratified by Saginaw County Peer Review Group 9-30-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Set 5/8" x 18" Re-bar with Saginaw Co. Re-Mon Bronze Cap Stamped #24612 in Ex. Mon. Box

| | | |
|------------------------------------|--|--------|
| SW Cor. Foundation House | N. 20° E. | 106.98 |
| Ctr. Hydrant | S. 01° W. | 46.72 |
| 1/2" Boat Spike in Mon. Box | S. 89° W., 14.42 S. 1/4 Cor. Sec. 32, T.13 N.-R.4 E. | |
| Nail & Cap in E. Face P. & T. Pole | N. 10° W. | 55.94 |
| Nail & cap in E Face T. Pole | N. 35° W. | 46.78 |

Signed by Ronald C. Prevost
Surveyor's Michigan License No. 24612

Date 11-24-93

