

**SURVEY & REMONUMENTATION**

NOV 1 2 1993

LIBER 1882 PAGE 1678

*Liber 6 page 132*

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Saginaw

(County)

Located In:

Corner Code #

12N 4E

G-7

- |                                    |   |       |   |       |       |
|------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey              | T | _____ | R | _____ | _____ |
|                                    | T | _____ | R | _____ | _____ |
|                                    | T | _____ | R | _____ | _____ |
|                                    | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R     |
|                                    | S | _____ | T | _____ | R     |
| 3. Miscellaneous Property in Sec.  | S | _____ | T | _____ | R     |
|                                    | S | _____ | T | _____ | R     |

RECORDED & FILED  
NOV 3 12 32 PM '93  
MILDRED J. GODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G-7 Sec. cor., Sec. 15, 16, 21 & 22, T12N-R4E

Wood post placed by J. Wampler D.S. in 1822  
S20°W 18 lks. (11.88') 16" Birch  
N51°W 24 1/2 lks. (16.17') 18" Birch

1938 survey by Redmond, County Surveyor, pg. 28, S.C.R.

1950's unrecorded City of Saginaw resurvey map #41

1929 Lathrup Park Subdivision, recorded in L. 5, pg. 25, S.C.R.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-7 Sec. cor., Sec. 15, 16, 21 & 22, T12N-R4E

Fnd. 2 1/2" cast iron shaft w/drill hole, in monument box, per City of Saginaw resurvey. Verified by measuring distance South to G-8, with 1938 survey by Redmond, County Surveyor and City of Saginaw resurvey and 1929 Lathrup Park Subdivision. Fnd. no evidence of original government corner

Approved by Saginaw County Peer Review September 23, 1993

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-7 Sec. cor., Sec. 15, 16, 21 & 22, T12N-R4E

Fnd. 2 1/2" cast iron shaft with drill hold in CL - CL intersection of State and Passolt Streets and is accepted as the best available evidence of the position of the original corner.  
S30°W 49.06' Spike w/tag #12018 in ESE face Util. Pole  
S59°E 48.47' PK w/tag #12018 in SW face Util. Pole  
N42°E 41.28' PK w/tag #12018 in SE face Util. Pole  
N28°W 105.90' SE cor. brick Landmark Ins. Agency bldg. #4012  
1'± above grade



Signed by John H. Rauser  
Surveyor's Michigan License No. 39096

Date 11/03/93

*11/18/93*