

Libar 6 Page 159

DEC 15 1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

File #

DEC 8 3 30 PM '93

MICHIGAN BOARD OF DEEDS
SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

COMMISSION

For corners in

Saginaw

(County)

Located In:

Corner Code -##

- 1. Public Land Survey T 12N. R 4E. I-1 (I-13)
T 12N. R 4E. J-1
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Brian D Ferguson, in a field survey on September 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-1 (I-13) Wood post set by J. Wampler in 1822. No evidence of original post exists

J-1 No corner set during original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 (I-13) Found 3/4" pipe in Monument Box. Used as common corner by sections 2 and 3 and 34 and 35 in 12-5. MDOT original route survey shows only one corner at this location, and is accepted as the best available evidence of the position of the original corner. Accepted by the Peer Review Group on 11/12/93

J-1 Found 3/4" pipe in Monument Box and is accepted as the best available evidence of the position of the original corner. Accepted by the Peer Review Group on 11/12/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 (I-13) 3" Brass Disk in monument box

J-1 3" Brass Disk in monument box

- N70°W 122.23' Top ctr of hydrant
- S50°W 87.18' Top ctr of hydrant
- S42°E 90.19' Top ctr of hydrant
- N24°E 121.00' Top ctr of hydrant

- West 15.70' Expan. joint, 1ft turn lane
- S50°W 110.48' Top ctr of hydrant
- N45°E 67.67' "+" in S. fce 12" round concrete sign support base
- S10°E 56.22' Nail & tag, SW fce pwr pole

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date _____

