

DEC 15 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED & FILED

For corners in
Saginaw
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 12N R 4E
T 12N R 4E

J-3
J-5

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Nov 5 9 12 AM '93
HILDEBRAND
REGISTER OF DEEDS
SACINAW COUNTY MICH.

Register of Deeds Stamp & File Number

Brian D Ferguson

September 30

19 93

I, Brian D Ferguson, in a field survey on September 30, 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-3 Wood Post set by J. Wampler in 1822. No evidence of original post exists.

J-5 Wood Post set by J. Wampler in 1822. No evidence of original post exists.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3										11			
4	7		8		9		10						
5										14			
6	18		17		16		15						
7													
8	19		20		21		22						
9													
10	30		29		28		27						
11													
12	31		32		33		34						
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3 Found 1" rod in monument box. Previous LCRC'S in L 2 Pg 180 and L 2 Pg 105. One recorded survey ties to this corner and is accepted as the best available evidence of the position of the original corner. Accepted by the Peer Review Group on 10/07/93

J-5 Found 3/4" pipe in monument box. Previous LCRC recorded in L 1 Pg 262. One unrecorded survey is tied to this corner and is accepted as the best available evidence of the position of the original corner. Accepted by the Peer Review Group on 10/07/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3 3" Brass Disk in monument box

S45°W 43.37' Top ctr hydrant
N45°W 45.72' PK nail in NE fce pwr pole
N45°E 37.96' PK nail in NW fce pwr pole
S45°E 36.75' PK nail in NE fce pwr pole

J-5 3" Brass Disk in monument box

N45°W 35.55' Ref disk NE fce pwr pole
N45°E 57.08' PK nail NW fce pwr pole
S45°E 71.73' Ref disk N fce pwr pole
S45°W 27.83' Ctr stm swr M.H.

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date 10-28-93

