

1993

DEC 29 3 20 PM '93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
Saginaw
(County)

FILED IN THE
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

	Located In:	Corner Code ##
1. Public Land Survey	T <u>12N</u> R <u>4E</u>	<u>K-1</u>
	T <u>12N</u> R <u>4E</u>	<u>K-2</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Libel 6 Page 191
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian D Ferguson, in a field survey on September 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 Wood Post set by J. Wampler in 1822. No evidence of original post exists.

K-2 Wood Post set by J. Wampler in 1822. No evidence of original post exists.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found 4" Brass disk w/ MDOT stamp in bridge deck. Previous LCRC in L 3 Pg 247. Two recorded subdivisions are tied to and verify this corner and is accepted as the best available evidence of the position of the original corner. Accepted by the Peer Review Group on 10/07/93

K-2 Found Concrete Monument on E'ly R/W line of I-675. Previous LCRC recorded in L 2 Pg 123. Two recorded surveys are tied to this corner and is accepted as the best available evidence of the position of the original corner. Accepted by the Peer Review Group on 10/07/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 4" Brass Disk in bridge deck w/MDOT stamp
North 47.70' Chisled + top guard rail base, N. side
South 47.55' Chisled + top guard rail base, S. side
N35°W 60.17' Chisled + top guard rail base, S. side
East 23.50' E'ly edge metal expansion joint, ctr line left turn lane

K-2 3" Brass Disk
N50°W 67.08' Chisled + @ sta 99+00 in ctr conc hdwl
South 54.26' Nail & tag N fce pwr pole
East 3.51' Wtrmain marker post
S50°W 57.61' NE bolt on E'ly leg sign base

Signed by B. D. Ferguson
Surveyor's Michigan License No. 26454

Date 10-29-93

