

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

304 8-5-98

SECTION
SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Lib 7 Page 204

For corners in

SAGINAW COUNTY

Located In: BLUMFIELD
Corner Code #

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

1998 OCT -5 A 9:48

RECORDED/FILED

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 12N R 6E B-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on JUNE 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	N
1	●											
2	6		5		4		3		2			
3												
4	7		8		9		10		11		13	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- B-1
- 1. CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY, ORANGE RISDON, APRIL 2, 1834. NO OTHER RECORDED INFORMATION FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-1
- SEARCHED APPARENT LOCATION OF CORNER AND FOUND 3/4" BAR, 13" LONG, 0.90' BELOW BITUMINOUS ROAD SURFACE. EXCAVATED AREA AND FOUND NO OTHER OBJECTS.
- ACCEPTED 3/4" BAR AS BEST AVAILABLE EVIDENCE OF THE POSITION OF ORIGINAL CORNER.
- 3/4" BAR SET ON LINE BETWEEN STANDARD CORNERS A-1, T12N, R6E AND B-13, T13N, R6E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-1
- REPLACED FOUND 3/4" BAR WITH 5/8" X 24" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.
- S32°W 43.55' SET 1/2" REBAR WITH CAP# 29240 WTI.
- N03°E 347.81' SET NAIL/TAG WEST FACE OF POWER POLE.
- EAST 28.99' TO PINCHED 3/4" PIPE, B-13, T13N, R6E.
- N70°E 53.93' SET 1/2" REBAR WITH CAP# 29240 WTI.

Signed by Dale Winiecke
Surveyor's Michigan License No. 41915

Date 9/30/98

