

1998

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

8-5-98

SECTION

LIBER 2084 PAGE 229

SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

for corners in

SAGINAW COUNTY

Located In: BLUMFIELD
Corner Code #

MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

1998 OCT -5 A 9:49

RECORDED/FILED

Lib 7 Page 207
Register of Deeds Stamp & File Number

| | | |
|---------------------------------|--------------------------|------------|
| Public Land Survey | T <u>12N</u> R <u>6E</u> | <u>E-1</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Lot No. _____, Recorded Plat _____

Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

DALE L. WINECKE, in a field survey on JUNE 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1

- POST SET BY ORANGE RISDON, D.S., APRIL 2, 1834. POST SET 35.08 CHAINS NORTH OF E-2 AND 59 LINKS EAST OF D-13, T13N, R6E. 22" BLACK ASH, S56°E, 7 LINKS; 14" ELM, S48°W, 67 LINKS.
- CERTIFICATE OF SURVEY, L.1307, P.633, D. BURGIN, PS#29240, (1991), DISTANCE FROM E-13, T13N, R6E TO E1, T12N, R6E. 38.94' R, 39.3' M.
- LCRC, L.1632, P.2013, R. PREVOST, PS#24612, (1983), FOUND 1/2" IRON.
- LCRC, L.2, P.516, J. QUIST, PS#25868, (1979), WITNESS FOR E-13, T13N, R6E, FOUND 5/8" REROD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1

SEARCHED APPARENT LOCATION OF CORNER AND FOUND A 5/8" REROD 0.35' BELOW ROAD SURFACE, EXCAVATED AREA, AND FOUND NO OTHER OBJECTS.
CHECKED WITNESSES FROM LCRC, L.1632, P.2013. WEST TO 1/2" IRON BAR E-13, T13N, R6E 39.33' (R) 38.97' (M); S45°E TO NORTHEAST CORNER RAIL ON END WING-WALL SUPPORT 21.00' (R&M). S50°W TO NORTHWEST CORNER RAIL ON END WING WALL SUPPORT 21.65' (R) 21.17' (M) NORTH TO CENTERLINE ASPHALT EAST & WEST 5.0' (R) 5.7' (M).
ACCEPTED 5/8" REROD AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1

RESET 5/8" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX ON CENTERLINE BEYER ROAD, 5.7' SOUTH OF PHYSICAL CENTERLINE WILSHIRE ROAD. WEST 38.97' (39.33' R) TO FOUND 5/8" REROD D-13, T13N, R6E. NORTH 24.19' TO WEST LEG OF ARROW SIGN. S18°E 37.21' TO SET NAIL WITH WTI TAGT IN TOP OF WOOD GUARD RAIL POST. N57°W 46.93' TO 3" PIPE, 4.5' HIGH. N61°E 41.39' TO SET 1/2" REBAR WITH CAP PS#29240 WTI.



Signed by Dale Winecke

Date 9/30/98

Surveyor's Michigan License No. 41915