

PEER GROUP
P.A. 340 OF 1990
SAGINAW COUNTY

1998 OCT 5 1998

LIBER 2084 PAGE 230

BDJ 8-5-98

SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SAGINAW COUNTY
(County)

Located In: **BLUMFIELD**
Corner Code #

1998 OCT - 5 A 9:49
MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

RECORDED/FILED

Liber 7 Page 208

Register of Deeds Stamp & File Number

Public Land Survey	T <u>12N</u> R <u>6E</u>	<u>F-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Lot No. _____, Recorded Plat _____

Private Claims _____

DALE L. WINIECKE, in a field survey on JUNE 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Description of original monument and accessories and/or subsequent restoration:

- F-1
- CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY BY ORANGE RISDON, D.S., APRIL 2, 1834.
 - CERTIFICATE OF SURVEY, L.856, P.697, P. CIOSEK, PS#25835, (1978); WITNESS FROM F-13, T13N, R6E CALLS OUT 3/4" PIPE 25.25' FROM F-13 (3/4" PIPE).
 - LCRC, L.2, P.516, J. QUIST, PS#25868, (1979); USED F-1 T12N, R6E AS WITNESS FOR F-13, T13N, R6E. 25.24' FROM F-13 TO F-1, (3/4" PIPE).
 - CERTIFICATE OF SURVEY, L.980, P.875, M. MACDONALD, PS#22438, (1985) USED F-1 T12N, R6E AS WITNESS FOR F-13, T13N, R6E (25.25' TO 3/4" PIPE).

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1

SEARCHED APPARENT LOCATION OF CORNER AND FOUND 3/4" PIPE, 13" LONG, 0.40' BELOW ROAD SURFACE. EXCAVATED PIPE AND FOUND IT TO BE SITTING ON TOP OF 1-1/4 X 34" LONG AXLE SHAFT AT 1.0' BELOW THE SURFACE. FOUND NO OTHER OBJECTS IN THE AREA. CHECKED DISTANCE FROM F-1 T12N, R6E TO F-13, T13N, R6E 25.24' (R) AND 25.25' (M). ACCEPTED 3/4" PIPE AS BEST AVAILABLE EVIDENCE OF THE POSITION OF ORIGINAL CORNER.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1

REPLACED FOUND 3/4" PIPE WITH 5/8"x 24" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX. 73.30' EAST OF CENTERLINE NORTHBOUND LANE M-15. NORTH 1.0' TO CENTERLINE WILSHIRE ROAD. S07°W 38.42' TO CHISELED "X" ON CONCRETE BOX CULVERT OVER CENTERLINE DITCH. N68°E 57.20" TO NAIL/TAG IN SOUTH FACE TELEPHONE RISER BOX. N73°E 123.51 TO SET NAIL WITH WTI TAG IN SOUTH FACE POWER POLE. S57°E 117.02 TO SET NAIL WITH WTI TAG IN SOUTHWEST FACE OF POWER POLE.

Signed by Dale Winiecke
Surveyor's Michigan License No. 41915

Date 9/20/98

