

SAGINAW COUNTY  
REMONUMENTATION

APR 2 1999

LIBER 2084 PAGE 231

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

304 8-19-98

SAGINAW COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in  
SAGINAW COUNTY  
(County)

Located In: BLUMFIELD  
Corner Code #

Public Land Survey	T <u>12N</u> R <u>6E</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1998 OCT -5 A 9:49  
 MILDRED M. DODAK  
 REGISTER OF DEEDS  
 SAGINAW COUNTY, MI  
 RECORDED/FILED  
 Liber 7 Page 209  
 Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

Private Claims \_\_\_\_\_

DALE L. WINIECKE, in a field survey on JUNE 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-1
1. POST SET BY ORANGE RISDON D.S., APRIL 2, 1934.  
12" ELM, S62°E 11 LINKS, 12" ELM, S55°W 55 LINKS.
  2. CERTIFICATE OF SURVEY RECORDED IN L.701, P.281, L. MCGINNIS, PS#18999, (1973), DISTANCE TO G-13, T13N, R6E.
  3. CERTIFICATE OF SURVEY L.1434, P.341, E. GOSS, PS#16040, (1974), FOUND RAILROAD SPIKE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1

SEARCHED APPARENT LOCATION OF CORNER AND FOUND RAILROAD SPIKE. EXCAVATED AREA UNDER RAILROAD SPIKE AND FOUND NO OTHER OBJECTS. ALSO FOUND 1" PIPE. EXCAVATED AREA UNDER THE 1" PIPE AND FOUND 3" ROUND CLAY MONUMENT AT 1.35' BELOW SURFACE.  
 CHECKED WITNESSES FROM 1953 SPICER ENGINEERING NOTES. NORTHEAST TO CENTER OF TELEPHONE POLE 97.55' (R), TO NAIL & TAG IN NORTHWEST FACE OF TELEPHONE RISER POLE 98.72' (M)  
 ACCEPTED 1" PIPE AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1

REPLACED FOUND 1" PIPE WITH 5/8" X 24" ROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.  
 NORTH 2.7' TO PHYSICAL CENTERLINE OF WILSHIRE ROAD.  
 S88°W 44.18' TO RAILROAD SPIKE G-13, T13N, R6E.  
 S68°E 10.70' TO 1/2" REBAR  
 N82°W 214.91' TO NAIL & TAG IN NORTH FACE TELEPHONE RISER BOX POLE.  
 S80°W 251.79' TO NAIL & TAG IN NORTH FACE OF POWER POLE.  
 N82°E 98.72' TO NAIL & TAG IN NORTHWEST FACE OF TELEPHONE BOX RISER POLE.

Signed by Dale Winiecke

Date 9/30/98

Surveyor's Michigan License No. 41915

