

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY  
*BLD 8-19-98*

SEP 2 1999

LIBER 2084 PAGE 232

SAGINAW COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SAGINAW COUNTY  
(County)

Located In: **BLUMFIELD**  
Corner Code #

- 1. Public Land Survey      T 12N R 6E      H-1
- T    R
- T    R
- T    R
- 2. Property Controlling    S    T    R
- in Section                S    T    R
- 3. Miscellaneous            S    T    R
- Property in Sec.        S    T    R

RECORDED/FILED

1998 OCT - 5 A 9:49  
MILDRED H. DODDAX  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

*Liber 7 Page 210*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, DALE L. WINIECKE, in a field survey on JUNE 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-1
- 1. CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY BY ORANGE RISDON, D.S., APRIL 2, 1834.
- 2. LCRC. L.2, P.80, E. GOSS, PS#16040, (1972), SET IRON.
- 3. CERTIFICATE OF SURVEY, L.1366, P.65, L. MCGINNIS, PS#18999, (1972), SET IRON,
- 4. CERTIFICATE OF SURVEY, L.1366, P.66, L. MCGINNIS, PS#18999, (1972), SET IRON,
- 5. CERTIFICATE OF SURVEY, L.1366, P.68, L. MCGINNIS, PS#18999, (1972), SET IRON,
- 6. CERTIFICATE OF SURVEY, L.929, P.827, J. FOKENS, PS#21567, (1981), DISTANCE FROM H-13, T13N, R6E
- 7. CERTIFICATE OF SURVEY, L.1434, P.341, E. GOSS, PS#16040, (1974), FOUND IRON.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1

SEARCHED APPARENT LOCATION OF CORNER AND FOUND 3/8" X 18" LONG REROD. EXCAVATED AREA UNDER REROD AND FOUND NO OTHER OBJECTS.

CHECKED WITNESSES FROM L.1366, P.65, P.66, P.68 AND LCRC L.2, P.80; S10°E TO FACE OF POWER POLE 68.15' (R&M); NORTHWEST TO NAIL IN TELEPHONE POLE 38.75' (R), TO NAIL IN TELEPHONE BOX RISER POLE 38.42' (M).

SURVEY IN L.929, P.827 USES H-1 AS A WITNESS TO H-13, T13N, R6E. GLO PRORATED DISTANCE (69.5 LINKS, 45.87')

FITS DISTANCE AS MEASURED IN FIELD, 45.83' (M).

ACCEPTED THE 3/8" REROD AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1

REPLACED FOUND 3/8" REROD WITH 5/8" X 24" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.

NORTH 4.9' TO CENTERLINE WILSHIRE, 2.4' WEST TO CENTERLINE CALLAHAN ROAD.

WEST 45.83' TO H-13, T13N, R6E, FOUND RAILROAD SPIKE.

S10°E 68.65' SET NAIL/TAG IN NE FACE OF POWER POLE.

S48°E 227.67' TO THE NORTHWEST CORNER OF FOUNDATION HOUSE#10540.

S24°W 9.15' TO EAST LEG OF ARROW SIGN.

Signed by Dale Winiecke  
Surveyor's Michigan License No. 41915

Date 9/30/98