

SAGINAW COUNTY
Blumfield 8-19-98

SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SAGINAW COUNTY
(County)

Located In: BLUMFIELD
Corner Code #

RECORDED/FILED
1998 OCT -5 A 9:49
MILCREG M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

Lib 7 Page 211
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 12N R 6E I-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on JUNE 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- I-1
- 1. POST SET BY ORANGE RISDON D.S., APRIL 2, 1834; 10" WHITE MAPLE, S24°W, 30 LINKS; 9" WHITE MAPLE, S50°E; 50 LINKS.
- 2. LCRC, L.2, P.80; E. GOSS, PS16040, (1972), SET IRON.
- 3. CERTIFICATE OF SURVEY, L.1366, P.65; L. MCGINNIS, PS#18999,(1972), SET IRON.
- 4. CERTIFICATE OF SURVEY, L.1366, P.66; L. MCGINNIS, PS#18999,(1972), SET IRON.
- 5. CERTIFICATE OF SURVEY, L.1366, P.68; L. MCGINNIS, PS#18999,(1972), SET IRON.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1

SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 3/8" REROD 0.75' BELOW SURFACE OF GRAVEL ROAD. NOTHING FOUND BELOW THE POINT DURING EXCAVATION.
NO WITNESSES REMAIN FROM PREVIOUSLY RECORDED INFORMATION.
DISTANCE FROM I-13, T13N, R6E TO I-1 T12N, R6E CHECKS PER GLO (56 LINKS) 36.96' (R), 36.95' (M).
ACCEPTED THE 3/8" REROD AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1

REPLACED FOUND 3/8" REBAR WITH A 5/8" X 24" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX. NORTH 8.0' TO PHYSICAL CENTERLINE WILSHIRE ROAD, EAST 5.0' TO CENTERLINE GERA ROAD.
WEST 36.95' TO FOUND 3/4" PIPE, I-13, T13N, R6E.
N03°E 28.57' TO WEST LEG ARROW SIGN.
N52°E 65.49' SET 1/2" REBAR WITH CAP PS#29240.
N68°W 34.58' SET 1/2" REBAR WITH CAP PS#29240.
S24°W 38.16' SET 1/2" REBAR WITH PS#29240.
S80°W 34.18' TO EAST LEG OF ARROW SIGN.

Signed by Dale Winiecke
Surveyor's Michigan License No. 41915

Date 9/30/98

SAGINAW COUNTY
REGISTER OF DEEDS

SEP 28 1998

SECTION