

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 SEP 26 P 3: 30

For corners in

<u>Saginaw</u> (County)	Located In: BLUMFIELD	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>6E</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2027 PAGE 475

Liber 7 Page 166

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael J. MacDonald, in a field survey on JUNE 26, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	I
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-1
1834 GLO, Risdon, D.S.; Beach 9 S77E 10lks, W.O. 38 N77W 33lks
- 1870 Cranston, C.S.; survey in E1/2 sec. 6, T12N, R7E; no object stated, no wits. given
- 1893 Felton, C.S.; prev. set by Pettibone; stone and drain tile at corner, no wits. given
- 1963 R.J. Black; survey; set nail by prorated meas.; S83W 22' to road sign, N60E 28.85' to mail box
- 1988 Ledy, PS # 21575; LCRC p.55, Fnd 1/2" rod, SE to NW cor of HSE 124.82', NE to nail in fenc. cor. 54.18', E,NE to nail in PP 68.16'
- 1994 Ledy, PS # 21575; 1993 Bay Co. Remonumentation, LCRC L. 003, P.75; Fnd. 1/2" rod; Accepted by Bay Co. Peer Group; Replaced 1/2" rod with 5/8" rod and Bay Co. Remon. Cap.
- 1996 Field, PS #37276; Tuscola Co. Remonumentation, LCRC Denmark, P.86, accepted Bay Co. Remon Cap

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

6-26-97 PJA

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-1
Found 5/8" rered with Bay County Remonumentation cap PS #21575 in monument box . 1.5' east of the centerline of Reese Road north and south and 1.5' south of the centerline of VanGiesen road to the east.

Accepted the found Bay County Remonumentation Monument as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 Held 5/8" Rerod with Bay County Remonumentation cap PS #21575 in monument box

- N 48° E 54.15' found nail in SE face fence post.
- N 56° E 67.90' set nail and tag in NW face of power pole.
- N 70° E 43.47' to south edge of stop sign post.
- S 75° E 62.47' to north edge of Denmark Township sign post.
- S 51° E 124.69' to NW corner of house.
- West 17.55' to south edge of south sign post leg.

SURVEY &
REMONUMENTATION

MAR 18 1998

SECTION

Signed by Michael J. MacDonald

Date 9/25/97

Surveyor's Michigan License No. 22438

