

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 SEP 26 P 3: 30

For corners in

<u>Saginaw</u> (County)	Located In: <u>BLUMFIELD</u>	Corner Code #
1. Public Land Survey	<u>T12N R6E</u>	<u>M-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2027 PAGE 476

Sheet 7 Page 167

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael J. MacDonald, in a field survey on AUGUST 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2 SET POST BY J. WAMPLER D.S.
WHITE OAK 34" S 64°E 25 L.
ASH 7" N 28°W 17 L.

SPICER NOTES DATED 1/27/71, SET NAIL W1/4 COR SEC 6, T13N, R6E
SPICER NOTES DATED OCT 1975, FOUND NAIL, SET 3/4" PIPE
LEDY L.C.R.C., TUSCOLA CO. DENMARK P.5, FOUND 3/4" PIPE, 1988
ROWE SURVEY, L. 1403, P.1125, FND. 1/2" REROD W/CAP, 1973

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

9-18-97 BDA

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 FOUND MONUMENT BOX WITH 5/8" REROD IN THE CENTERLINE OF REESE ROAD. ALSO FOUND 1/2" REROD AT THE EAST EDGE OF THE ROAD USED IN 1973 ROWE SURVEY. THE 1/2" REROD IS 9.38' FROM THE 5/8" REROD IN MON BOX. ANGLE(L3-M3-M2) AND DISTANCE(M2-M3) FROM SPICER NOTES DATED 1971 AND 1975 AND WITNESSES FROM L.C.R.C BY LEDY VERIFY THE LOCATION OF THE FOUND 5/8" IN MONUMENT BOX. 5/8" REROD IN MONUMENT BOX ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 PLACED SAGINAW COUNTY REMONUMENTATION CAP ON TOP OF FOUND 5/8" REROD IN MONUMENT BOX

N 20° E 203.11' SET NAIL & TAG IN WEST FACE PP
N 30° E 32.08' SET CAPPED 1/2" REROD
S 25° E 28.71' SET CAPPED 1/2" REROD
S 15° E 232.16 SET NAIL AND TAG IN WEST FACE PP
S 40° W 21.80' SET CAPPED 1/2" REROD
N 15° W 34.86' SET CAPPED 1/2" REROD
EAST 9.38' TO FND 1/2" REROD

SURVEY &
REMONUMENTATION

MAR 18 1998

SECTION

Signed by Michael J. MacDonald

Date 9/25/97

Surveyor's Michigan License No. 22438

