

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 SEP 26 P 3:30

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2027 PAGE 477

Liber 7 Page 168
Register of Deeds Stamp & File Number

For corners in

Saginaw Located In: BLUMFIELD Corner Code #
(County)

1. Public Land Survey T 12N R 6E M-3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael J. MacDonald, in a field survey on JUNE 25, 1997
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as
required in the current manual of survey instructions of the United States Department of the Interior,
Bureau of Land Management or by a decree of a Court of Law and /or that the corner points
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of
Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,
recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-3 POST SET BY J. WAMPLER D.S.
SUGAR 17" S 27°E 17 L.
BEECH 7" N 2°W 5 L.

L.C.R.C.-L.3,P.164, BY JOHN MARTIN, FND 1/2" ROD

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

6-26-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 FOUND 1/2" REROD IN MONUMENT BOX PER L.C.R.C.. NO OTHER MONUMENTATION WAS FOUND IN THE AREA. MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 REPLACED 1/2" REROD IN MONUMENT BOX WITH A SAGINAW COUNTY REMONUMENTATION CAP PS # 22438 ON A 5/8"x 18" LONG REROD.

N 30° E 26.99' SET CAPPED 3/8" REROD
N 30° E 58.14' SET NAIL AND TAG IN WEST FACE 18" TWIN ASH
N 45° E 20.40' SET MAG NAIL AND TAG IN THE TOP OF CONC. HEADWALL
S 45° E 27.87' SET MAG NAIL AND TAG IN THE TOP OF CONC. HEADWALL
S 20° E 35.15' SET CAPPED 3/8" REROD
S 35° W 29.76' SET MAG NAIL AND TAG IN THE TOP OF CONC. HEADWALL
S 50° W 44.32' SET CAPPED 3/8" REROD
N 70° W 86.58' SET NAIL AND TAG IN NORTH FACE PP

SURVEY &
REMONUMENTATION

MAR 18 1998

SECTION

Signed by Michael J. MacDonald

Date 9/25/97

Surveyor's Michigan License No. 20438

