

SURVEY & REMONUMENTATION

MAR 18 1998

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

<u>Saginaw</u> (County)	Located In: <u>BLUMFIELD</u>	Corner Code # <u>M-5</u>
1. Public Land Survey	<u>T12N R6E</u>	<u>M-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

1997 SEP 26 P 3: 30

MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

NUMBER 2027 PAGE 479

Sheet 7 Page 170
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael J. MacDonald, in a field survey on JUNE 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5 SET POST BY J. WAMPLER D.S.
BEECH 12° N 23° E 18 L.
BEECH 12° S 16° W 29 L..

L.C.R.C., L.2,P. 129- 1973- MARTIN, FND 3/4" BAR IN MON. BOX
 RECORDED SURVEY L.767, P.537-1975-MCGINNIS, FOUND 3/4" IRON IN MON. BOX
 L.C.R.C., L.3,P. 205- 1976- MCGINNIS, FND3/4' IRON IN MON. BOX
 RECORDED SURVEY L.1499, P.933-1976-HAMMOND, FOUND MON. BOX WITH 3/4" BOLT
 RECORDED SURVEY, L.1563, P.804- 1978- DUNTIN, NO MONUMENT CALLED OUT, NO WIT.
 RECORDED SURVEY., L.1563, P.423, 1978- DUNTON, FND MON. BOX WITH 3/4" IRON BAR
 RECORDED SURVEY, L. 1619, P.424, 1978- DUNTON, FND MON. BOX WITH 3/4" IRON
 L.C.R.C., L.1619,P. 539- 19786- ROWE, FND MON. BOX WITH 3/4" IRON BAR
 L.C.R.C., TUSCOLA CO. DENMARK,P. 539- 1991- BROWN, FND1 1/4" BAR IN MON. BOX
 TUSCOLA CO. PLAT, L. 316, P. 246
 RECORDED DURSEL PLAT

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY
6-26-97 [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 FOUND 3/4" IRON BAR IN MONUMENT BOX AT CONSTRUCTION CENTERLINE OF M-81, NO OTHER MONUMENTATION IN THE AREA.
 RECORDED WITNESSES (L.C.R.C., L.2,P. 129; SURVEY L.767, P.537; L.C.R.C., L.3,P. 205; SURVEY L.1499, P.933; SURVEY, L.1563, P.804;
 SURVEY, L.1563, P.423; SURVEY, L. 1619, P.424; L.C.R.C., L.1619,P. 539 ; L.C.R.C., DENMARK,P. 539 VERIFY THE LOCATION OF THE 3/4" BAR
 IN THE MONUMENT BOX. MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 FOUND 3/4" BAR IN MONUMENT BOX, UNABLE TO SET SAGINAW REMONUMENTATION CAP ON THE BAR.

N 35°E 43.27' SET NAIL AND TAG IN SE FACE PP
 S 33°E 43.52' SET NAIL AND TAG IN NE FACE PP
 S 30°W 56.64' SET NAIL AND TAG IN EAST FACE PP
 S 65°W 100.64' SET NAIL AND TAG IN SE FACE PP
 N 45°W 48.56' SET NAIL AND TAG ON TOP OF SE CORNER OF LANDSCAPE TIMBER
 ON CENTERLINE OF CONC. JOINT EAST AND WEST ALONG M-81
 ON CENTERLINE OF CONC. JOINT NORTH AND SOUTH ALONG REESE ROAD



Signed by Michael J. MacDonald

Date 9/25/97

Surveyor's Michigan License No. 22438