

**SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED/FILED

1997 SEP 26 P 3: 31

MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.
LIBER 2027 PAGE 483

Lib 7 Page 174

Register of Deeds Stamp & File Number

For corners in

<u>Saginaw</u> (County)	Located In: BLUMFIELD	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>6E</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael J. MacDonald, in a field survey on JUNE 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-9 SET POST BY J. WAMPLER
SUGAR 16" N 42° W 17 L.
IRONWOOD 6" S 38° E 9 L.

L.C.R.C. L.1, P. 98, MARTIN, 1971, FND 3/4" PIPE
L.C.R.C., TUSCOLA CO. DENMARK, P.3, DORCEY, 1972, FND 3/4" PIPE

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY
6-26-97 [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 FOUND 3/4" PIPE IN MONUMENT BOX (RECORDED L.C.R.C L. 1, P. 98 AND TUSCOLA CO. L.C.R.C. DENMARK P.3). RECORD WITNESSES VERIFY LOCATION OF 3/4" PIPE. MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 3/4" PIPE IN MONUMENT BOX WITH SAGINAW COUNTY REMONUMENTATION CAP ON 5/8" x 18" LONG REROD

N 45° E 43.62' SET NAIL AND TAG IN SE FACE PP
S 45° E 47.81' SET NAIL AND TAG IN THE TOP CENTER OF A CUTOFF UTILITY POLE
S 10° W 35.50' TO NORTH FACE ROUND METAL STREET SIGN POST
N 45° W 33.70' SET CAPPED 3/8" REROD
N 50° W 50.14' SET NAIL AND TAG IN NE FACE 48" OAK
N 25° W 35.69' SET NAIL AND TAG IN NORTH END 18" CMP



Signed by Michael J. MacDonald

Date 9/25/97

Surveyor's Michigan License No. 22438

SURVEY &
REMONUMENTATION

MAR 18 1998

SECTION