

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE

RECORDED/FILED

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2028 PAGE 444

For corners in: BLUMFIELD TWP.

1997 OCT -3 A 8: 28

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

*Robert Page 189*

Register of Deeds Stamp & File Number

SAGINAW (County)	Located In:	Corner Code #
1. Public Land Survey	T 12N R 06E	M-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JULY 8 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1821 GLO; WAMPLER, D.S.; SET 1/4 SEC. POST; W. OAK 18 N13W 20 LKS., R. OAK 17 S40E 28 LKS.  
1972 CPCO; DORCEY, LS#9429; SET BOAT SPIKE BY SINGLE PROPORTION; NORTH 11.38' OCC LINE TO WEST, NE 44.00' RD. SIGN POST, SE 46.50' 18" MAPLE  
1972 DORCEY, LS#9429; LCRC DENMARK TWP. PG.4; SAME OBJECT AND WITS AS 1972 CPCO SURVEY ABOVE  
1985 DUNTON, LS#23503; SURVEY L.553, PG.484; FND. SPIKE; NORTH 11.4' OCC LINE TO WEST, WEST 8.5' C/L PVMT, NORTH 13' C/L PVMNT EAST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997 ROWE; FIELD, PS#37276; FND. 1/2" BOAT SPIKE 9' E. OF C/L REESE ROAD & 11' S. OF C/L KREUGER ROAD TO E.; RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. BOAT SPIKE IS IN SAME POSITION AS 1985 DUNTON SURVEY CITED IN SECTION A. ABOVE

ACCEPTED FND. BOAT SPIKE AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-12 REPLACED FND. BOAT SPIKE W/ 5/8" ROD & STD. REMON. CAP IN MON. BOX  
S70°E, 24.84' CHIS. NOTCH IN SW END ARCH CULVERT  
N40°E, 40.92' CHIS. NOTCH IN NE END ARCH CULVERT  
N40°W, 30.33' 1/2" ROD W/CAP #37276  
S40°W, 32.69' 1/2" ROD W/CAP #37276  
N70°W, 27.96' S. EDGE OF S. LEG SIGN POST



Signed by Jonathan M. Field Date 9-25-97  
Surveyor's Michigan License No. 37276

SURVEY &  
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1974

REVISED MAY 14, 1975  
REVISED JAN. 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1983

MAR 18 1998

SECTION