

SAGINAW COUNTY REMONUMENTATION PROJECT
APPROVED BY PEER GROUP
P.A. 345 OF 1990
LAND CORNER RECORDATION CERTIFICATE
SAGINAW COUNTY
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 14 4 08 PM '94

REGISTER OF DEEDS
SAGINAW COUNTY MICH.

For corners in SURVEY 60
Saginaw County

Corner Code #

- 1. Public Land Survey T 13N R 3E C-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Handwritten: Liber 6 Page 231

Register of Deeds Stamp & File Number

I, John H. Rauser, in a field survey on May/June 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (C-1/ Sec. Cor., Sec. 5 & 6, T12N-R3E - Sec. 31 & 32, T13N-R3E
C-13) No record of post set in 1822 by J. Wampler. Original notes state corner "in run inaccessible on account of flood". No reference given, when running S. line of T13N-R3E. When running North between Sec. 5 & 6, notes state "Int. town line at post". No reference given.
1972 L.C.R.C. by Gerald R. McKelvey, P.S. #19001, Recorded L.1, Pg.169, Saginaw County Records.
1975 Act 132 by Arthur H. Leach, P.S. #7236, Recorded L.1452, Pg.934-935, Saginaw County Records.
Act 132 by Arthur H. Leach, P.S. #7236, Recorded L.1448, Pg.1094, Saginaw County Records.
L.C.R.C. by Arthur H. Leach, P.S. #7236, Recorded L.3, Pg.112, Saginaw County Records.
1976 Act 132 by Arthur H. Leach, P.S. #7236, Recorded L.1452, Pg.939, Saginaw County Records. Recorded L.1469, Pg.1179, Saginaw County Records. Recorded L.1489, Pg.1006, Saginaw County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (C-1/ Sec. Cor., Sec. 5 & 6, T12N-R3E - Sec 31 & 32, T13N-R3E
C-13) Found no evidence of original government corner. Found 3/4" pipe as reset by Saginaw County Road Commission after road relocation, pipe fit well with Art Leach Surveys of record, (R=2618.49' C-13 to C-12) M=2618.44', no existing recorded witnesses due to road relocation, and is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (C-13) Sec. Cor., Sec. 5 & 6, T12N-R3E - Sec 31 & 32, T13N-R3E
Rest 5/8" rerod w/brass cap stamped Saginaw County Monument, P.S. #39096 in existing monument box.
N52°W 60.83' Set spike w/tag #39096 in S. fce. Power Pole (fnd. spike E. fce. 60.80')
N64°W 115.78' Set spike w/tag #39096 in NNE fce. Power Pole
N35°E 63.25' Fnd. spike w/flag in SE fce. 8" Elm
S80°E 59.23' Set spike w/tag #39096 in N. fce. 36" Oak
S35°E 76.37' Fnd. spike w/flag in SW fce. 8" Elm

Signed by John H. Rauser Date
Surveyor's Michigan License No. 39096

