

APPROVED BY PEER GROUP

LIBER 1924 PAGE 776

P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT

DEC 14 4 08 PM '94

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

MICHIGAN STATE BOARD OF SURVEYORS
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

For corners in Saginaw (County) REMONUMENTATION Located In:

Corner Code #

APR 24 1995

- 1. Public Land Survey T 13N R 3E F-13
COMMISSION R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Lib 6 Page 230

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, in a field survey on May 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F-13) Standard S 1/4 cor., Sec. 33, T13N-R3E
Not set by J. Wampler during original 1822 government survey, corner fell in Indian Reserve. Wood post set by J. Mullett, Deputy Surveyor, 1839 during survey of Saginaw Reserve N65°W 9 lks. (5.94') 10" Beech S20°W 21 lks. (13.86') 12" Beech
1968 Witnesses by Saginaw County Road Commission
1972 Act 132 by John W. Martin, P.S. #4699, rec. in L. 1391, pg. 476, Saginaw County Records.
1973 L.C.R.C. by John W. Martin, P.S. #4699 rec. in L. 2, pg. 106, Saginaw County Records.
1990 Act 132 by Duane F. Levy, P.S. #21575, rec. in L. 1796, pg. 1111, Saginaw County Records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-13) Standard S 1/4 cor., Sec. 33, T13N-R3E
Found no evidence of original government corner. Found 3/4" pipe in mon. box as per record as stated in "A" above and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-13) Standard S 1/4 cor., Sec. 33, T13N-R3E
Reset 5/8" rerod w/brass cap stamped Saginaw County Monument, P.S. #39096, in existing monument box.
North 51.95' Set PK w/tag #39096 in SE fc. new power pole
S23°W 53.24' Fnd. spike in E. fc. Utility Pole
S23°W 52.94' Fnd. PK NE fc. Utility Pole
S64°W 76.68' Fnd. spike S. fc. Guy Pole
S64°W 51.85' F-1, T12N-R3E

Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date Jan 15, 1995

