

APPROVED BY PEER GROUP

P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT

SAGINAW COUNTY

LAND CORNER RECORDATION CERTIFICATE

DEC 14 4 08 PM '94

Filing Requirement of Act 74, Mich. P.A. 1970

THE STATE OF MICHIGAN REGISTER OF DEEDS SAGINAW COUNTY MICH.

For corners in SURVEY & REMONUMENTATION Saginaw (County) Located in:

Corner Code #

- 1. Public Land Survey T 13N R 3E COMMISSION T R T R
2. Property Controlling in Section S T R S T R S T R S T R
3. Miscellaneous Property in Sec. S T R S T R

H-13

Lib 6 Page 229

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Table with 13 rows and 12 columns (A-L) containing numbers 1-36.

I, John H. Rauser, in a field survey on June 1 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H-13) S 1/4 cor., Sec. 34, T13N-R3E Wood post set by J. Wampler, 1822 N86°E 14 lks. (9.24') 20" Beech S47°W 34 lks. (22.44') 30" Pine 1956 Plat of Riverdale Acres, rec. in L. 10, pg. 41, Saginaw County Records. 1972 Act 132 by John W. Martin, P.S. #4699, rec. in L. 1498, pg. 240, Saginaw County Records. 1972 L.C.R.C. by John W. Martin, P.S. #4699, rec. in L. 1, pg. 260, Saginaw County Records. 1979 L.C.R.C. by Ronald C. Prevost, P.S. #24612, rec. in L. 5, pg. 27, Saginaw County Records. Plat of Long Acres Estates rec. in L. 16, pg. 17-18, Saginaw County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-13) S 1/4 cor., Sec. 34, T13N-R3E Found 3/4" pipe in asphalt surface as per record as stated in "A" above and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-13) S 1/4 cor., Sec. 34, T13N-R3E Reset 5/8" rerod w/brass cap stamped Saginaw County Monument, P.S. #39096. Placed monument box flush w/pav't. N25°W 33.79' Fnd. PK NNE fc. Utility Pole S67°W 87.40' Top center hydrant N42°E 81.79' SW cor. brick hse. #5020 S70°W 100.62' Fnd. PK S. fc. Utility Pole West 58.02' H-1, T12N-R3E

Signed by John H. Rauser Date

Surveyor's Michigan License No. 39096

