

12-7-94 *BDK*
 For corners in **SURVEY & REMONUMENTATION**
 Saginaw (County) Located In: _____

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Liber 6 Page 269

1. Public Land Survey **APR 24 1995** T 13 N, R 3 E. I-13
 T _____ R _____
COMMISSION T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED & FILED
 Dec 27 9 16 AM '94
 MILEAGE: 1.00 DAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.
 Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 Post by Joseph Wampler in 1822.
 Beech 4" S.23°W. 3 Lks.
 Beech 14" N.32°W. 16 Lks.
 SE corner Sec 34, referred to in Spicer field notes of 1964 (Tittabawassee Bridge) as being set by M.S.H.D.
 Recorded survey 1971 L.1348, P.937 (shown on)
 LCRC 1981 L.5, P.160, Prevost 1/2" Rod in Mon. Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found 1/2" rod in Mon. Box & Recorded Witnesses
 West 36.30 NE corner Sec 3, T.12 N.-R.3 E.
 N.30°W. 54.80 NE corner concrete bridge
 S.80°W. 42.90 SE corner concrete bridge

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Placed 5/8" Rerod & 2 1/2" Saginaw Co. Bronze Cap in existing Mon. Box in place of round 1/2" rod
 West 36.30 corner I-1, NE of 3, NW of 2, T.12 N.-R.3 E.
 N.30°W. 54.70 NE corner concrete bridge
 S.80°W. 42.90 SE corner concrete bridge
 S.88°W. 27.75 P.K. Nail E face P Pole



Signed by Ronald C. Prevost
 Surveyor's Michigan License No. 24612

Date 12-15-94