

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

12-13-94 *BR*

RECORDED & FILED  
 DEC 27 9 15 AM '94  
 MICHIGAN BOARD OF DEEDS  
 SAGINAW COUNTY MICH.

For corners in Saginaw SURVEY & REMONUMENTATION Located In: Corner Code #

1. Public Land Survey	T	13 NR	3 E.	J-13
APR 24 1995	T		R	
	T		R	
	T		R	
2. Property Controlling in Section	S		T	R
	S		T	R
3. Miscellaneous Property in Sec.	S		T	R
	S		T	R

*Sheet 6 Page 258*  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Ronald C. Prevost, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 J-13 Post by Joseph Wampler, 1822  
 Maple 14" S.13°W. 10 Lks.  
 Sugar 14" N.32°W. 7 Lks.  
 P.K. Nail set by Spicer Eng. 1968, on extension of N & S 1/4 Line fence in the N 1/2 of Sec 35 extended South to intersect the South Section line 26.30 feet East of corner J-1, T.12 N.-R.3 E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 J-13 Found P.K. Nail from 1968

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Replace P.K. Nail with 5/8" Rerod, 2 1/2" Saginaw Co. Bronze Cap & Mon. Box  
 South 2.1'± centerline bituminous surface E & W  
 West 26.32 to corner J-1, T.12 N.-R.3 E.  
 S.25°W. 58.95 Nail in N Face P.P.  
 S.20°W. 67.10 Center Plastic Cable Marker



Signed by Ronald C. Prevost  
 Surveyor's Michigan License No. 24612

Date 12-15-94