

APPROVED BY PEER GROUP
 P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT
 SAGINAW COUNTY LIBER 1925 PAGE 335

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Saginaw

SURVEY & Located In:

Corner Code #

REMONUMENTATION

- | | | | | |
|------------------------------------|---|-------|------|------|
| 1. Public Land Survey | T | 13 NR | 3 E. | K-13 |
| | T | | R | |
| | T | | R | |
| | T | | R | |
| | T | | R | |
| 2. Property Controlling in Section | S | | R | |
| | S | | R | |
| 3. Miscellaneous Property in Sec. | S | | R | |
| | S | | R | |

APR 24 1995

COMMISSION

RECORDED & FILED
 DEC 27 9 15 AM '94
 MICHIGAN BOARD OF LAND SURVEYORS
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

Libert Page 261

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 Post by Joseph Wampler, 1822
 Elm 12" N.81°E. 60 Lks.
 Elm 11" N.69°W. 12 Lks.
 SCRC Witnesses 1974 3/4" Iron Pipe 6" Below Bit.
 LCRC Witnesses 1976 3/4" Rod L.3, P.213

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found 3/4" bar in Mon. Box and Recorded Witnesses.
 West 23.70 N.W. Cor., Sec. 1, T.12 N.-R.3 E. (23.86)
 SW 62.30 C.P. Co. Tag E. Face P.P. (S.70°W., 62.05 Nail E. Face P. Pole)

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Placed 2 1/2" Saginaw County Bronze Cap on Existing 3/4" Bar in Existing Mon. Box.
 N.45°E. 57.25 Nail & Washer S. Face 30" Maple
 West 23.86 Corner K-1
 S.70°W. 62.05 Nail in E. Face P. Pole
 N.40°W. 69.45 SE Cor. Post Chain Link Fence



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612