

12-13-94 [Signature]

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Saginaw SURVEY & REMONUMENTATION Located In:

Corner Code ##

- 1. Public Land Survey T 13 N. R 3 E. L-13
 APR 24 1995
 COMMISSION
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Dec 27 9 15 AM '94
 MICHIGAN BOARD OF LAND SURVEYORS
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

RECORDED & FILED

Lib 6 Page 253
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald C. Prevost, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-13 Post by Joseph Wampler, 1822
 Sugar 26" S.80°E. 15 Lks.
 Beech 9" N.5°W. 24 Lks.
 LCRC L.3, P.213 Leach, 1976, 1/2" Square Rod Flush with Bit, found
 3/4" Pipe set in 1977 Spicer Eng. in line with remains of fence to North, falls 6' West of corner L-1, T.12 N.-R.3 E.
 LCRC L.4, P.85 Martin, 1977 3/4" Pipe Set

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-13 Found 3/4" Pipe, 6.0' West of corner L-1, T.12 N.-R.3 E.
 LCRC L-3, P.213 is recorded as being L-13, T.13 N.-R.3 E., but actually is corner L-1, T.12 N.-R.3 E.

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13 Replace 3/4" Pipe with 5/8" Rerod, 2 1/2" Saginaw Co. Bronze Cap & Mon. Box
 East 6.0 corner L-1, T.12 N.-R.3 E.
 N.01°E. 45.3 Tel Riser
 N.10°W. 33.50 Gasline marker
 S.50°E. 51.30 Gasline marker
 South 36.50 Face 8" Ash



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612