

6-30 B.P.F.
For corners in

SEP 28 3 16 PM '99

Saginaw (County) Located In: Tittabawassee Twp. Corner Code #

1. Public Land Survey T 13N R 3E M-1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

MIDDLEBURY TWP
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2144 PAGE 736

Liber 8 Page 8
Register of Deeds Stamp & File Number

I, Roger P. Mahoney, in a field survey on 3-31, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-1 Post set by D.S. Joseph Wampler, 1822, common to T.13 & T.14 N & R.3 & 4 E. Ironwood 10" S.69°E., 19 Lks., Lynn 32" N.70°E., 12 Lks. This corner previously re-monumented as A-1, T.13 N.-R.4 E., in Liber 003 Pg 244 and A-13, T.14 N.-R.4 E., in Liber 003 Pg 246 Bay County Re-mon 1995 by Craig McVean PS #39088.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 Found 18" re-bar with Bay County Re-mon cap in mon box. Cap stamped #39088. As per recordings.

Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 18" re-bar with Bay Co. re-mon cap stamped #39088. N.44°E. 44.60 nail & tag N.W. side U.P. (recorded 44.60). N.42°W. 63.80 SE corner (1.0' UP) Block foundation building (R 63.80). S.33°E. 42.58 nail & tag NE face U.P. (record 42.58). S.47°W. 41.30 nail & tag N.W. face U.P. (record 41.30).



SURVEY & RE...

MAR 09 2000

SECTION

Signed by Roger P. Mahoney
Roger P. Mahoney

Date 9-27-99

Surveyor's Michigan License No. 41105