

6-30 BDF
For corners in

SEP 28 3 16 PM '99
MILBURN B. BAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

<u>Saginaw</u> (County)	Located In: <u>Tittabawassee Twp.</u>	Corner Code # <u>M-2</u>
1. Public Land Survey	T <u>13N</u> R <u>3E</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 2144 PAGE 735

Sheet 8 Page 7

Register of Deeds Stamp & File Number

I, Roger P. Mahoney, in a field survey on 3-31, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2 Post set by Joseph Wampler D.S. 1822
W Oak 32° S.43°W. 28 Lks.
Birch 14° N.41°W. 29 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 Found 3/4" pipe in mon box. Note: Witnesses in the Act 132 recordings below are checking with the first three witnesses shown below.
L.C.R.C L3 P206 McGinnis, 1976, 3/8" re-rod.
Act 132 L1416 P1168, 3/8" rod. Act 132 L1515 P871, 3/8" rod. Act 132 L1515 P490, 3/8" rod.
Act 132 L1518 P252, 3/8" rod. Act 132 L1541 P24 3/8" rod. Sag. Co. Rd. Comm. notes of 1980 3/8" iron.

Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Replaced 3/4" pipe with 5/8" rod & Saginaw Co. re-mon cap stamped #24612 in existing mon box.
S.35°W. 91.30 nail & tag E. side U.P. (record 91.1 pole).
S.45°E. 29.00 nail & tag NE side U.P.(record 28.47 pole).
N.40°W. 106.84 SE cor. block foundation house (record 106.84).
N.45°W. 75.92 set nail & tag in E. side 30" Maple.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY & RE-MONUMENTATION

MAR 09 2000

SECTION



Signed by Roger P. Mahoney
Roger P. Mahoney

Date 9-27-99

Surveyor's Michigan License No. 41105