

8-20-96 *[Signature]*

Saginaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Saginaw (County)	Located In:	Corner Code #
1. <u>Mittabawassee Township</u> Public Land Survey	T <u>13NR</u> 3E	<u>M-6</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

RECORDED & FILED
SEP 27 11 45 AM '89
MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.
Liber 1 Page 89
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael J. MacDonald, in a field survey on August 16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 Post set by J. Wampler D.S. in 1822.
L.C.R.C. - L. 4, P. 265, R. Prevost fnd 1" x 1" x 24" iron bar.
L.C.R.C. - L. 3, P. 103, A. Leach set PK nail 1/2 way on line between M-5 and M-7.
Recorded Surveys: L. 1666, P. 181; L. 1666, P. 193; L. 1645, P. 1163; L. 1441, P. 809.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Fnd 1/2" diameter x 18" long iron with square top 10" below surface surrounded by three rocks 4" to 8" diameter.
2624.05' (2623.83' - R) S of M-5 - did not find PK nail or witnesses noted in L.C.R.C. - L. 3, P. 103.
2620.88' (2620.62' - R) N of M-7.

Recorded Witnesses as follows: N 30° W 30.43' to nail and tag in E side double 20" Cottonwood (29.4' to face per Spicer notes) S 55° E 72.49' to nail and tag in SW side of 36" Willow (72.65' to face 6" Willow - R).
Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Replaced 1/2" iron with Saginaw County Remonumentation cap on 5/8" x 18" long rebar in monument box.
N 30° W 30.43' to nail and tag in E side of double 20" Cottonwood.
S 55° E 72.49' to nail and tag in SW side of 36" Willow.
N 80° E 107.26' to nail and tag in S side of 10" Ash.
S 20° W 152.24' to nail and tag in E side of pole.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 25 Sept 96

REMONUMENTATION

MAY 18 1997