

Saginaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Saginaw</u> (County)	Located In:	Corner Code #
Tittabawassee Township		
1. Public Land Survey	T <u>13NR</u> <u>3E</u>	<u>M-8</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

RECORDED & FILED  
 SEP 27 11 45 AM 1996  
 MILDRED N. BOGAK  
 REGISTER OF DEEDS  
 SAGINAW COUNTY MICH.

*Liber 7 Page 87*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael J. MacDonald, in a field survey on August 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-8 Post set by J. Wampler D.S. in 1822.

L.C.R.C. - by L. 2, P. 211 by A. Leach - set RR spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Fnd RR spike on line between M-7 and M-9 and 0.07' N of equal distance from M-7 and M-9.

Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Replaced RR spike with Saginaw County Remonumentation cap on 5/8" x 18" rebar in monument box.

- S 20° E 128.96' to nail and tag in W face of pole.
- N 20° E 142.12' to PK nail in W face of pole.
- S 85° E 150.20' to NW corner of attached to Hse. #7470.
- N 10° W 112.10' to chiseled notch in W end of 72' CMP.



Signed by Michael J. MacDonald  
Surveyor's Michigan License No. 22438

Date 25 Sept 96

MAY 16 1997