

Saginaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 7 Page 86

For corners in

Saginaw (County)	Located In:	Corner Code #
Tittabawassee Township		
1. Public Land Survey	T 13NR 3E	M-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTERED & FILED
SEP 27 11 45 AM 1986
HILDRED H. DOBAX
REGISTER OF DEEDS
SAGINAW COUNTY MICH.
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on August 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-9 Post set by J. Wampler D.S. in 1822.

L.C.R.C. - L. 1, P. 87, by R. Sides - fnd 1" Iron rod.

L.C.R.C. - L. 6, P. 38 by D. Ledy - fnd RR spike.

Recorded Surveys: L 1592, P. 752; L. 1489, P. 783.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Fnd RR spike 0.15' below road surface - also fnd 2" x 2" x 8" long wood stake with tack on top 0.45' below road surface 0.17' W and 0.13' N of RR spike.

RR spike accepted as the best available evidence of the position of the original corner.

Recorded Witnesses as follows:

N 75° E (E - R) 54.65' to nail in N face of U.P.
SE 22.74' (22.40' - R) to spike in guard rail post.
NE 31.55' (31.43' - R) to spike in guard rail post.
NW 45.64' to SE edge of MH cover.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Replaced RR spike with Saginaw County Remonumentation cap on 5/8" rered 18" long in monument box

N 75° E to nail in N face of pole.
N 40° W 132.60' to SE corner of garage attached to Hse. #7024.
NW 45.64' to SE edge of MH cover.
SE 22.74' to spike in guard rail post.
NE 31.55' to spike in guard rail post.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 25 Sept 96

MAY 1 8 1997