

Saginaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Saginaw Located in: Corner Code #
(County)
Kochville Township
1. Public Land Survey T 13NR 4E A-8
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

RECORDED & FILED
SEP 27 11 49 AM '96
MILDRRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

Liber 7 Page 84
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael J. MacDonald, in a field survey on August 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8 Post set by J. Wampler D.S. in 1822.

L.C.R.C. - L. 3, P. 240, by John Martin - fnd nail, set 3/4" pipe.
Recorded Surveys: L. 1729, P. 373.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8 Fnd 3/4" pipe 14" long at road surface.


Recorded Witnesses as follows:

N 30° E 105.10' to PK nail and cap on W side of P.P.
S 41.00' (41.02' - R) to RR spike at M-8, T13N, R3E.
Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 Replaced 3/4" pipe with Saginaw County Remonumentation cap on 5/8" rebar 18" long in monument box.

N 30° E 105.10' to PK nail and cap on W side of pole.
S 15° E 167.05' to nail and tag in W face of pole.
S 45° E 194.65' to SW corner of Hse. #7470.
N 15° W 72.05' to chiseled notch in W end of 72" CMP.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 25 Sept 96

MAY 16 1997