

Saginaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Lib 7 Page 82

For corners in

Saginaw	Located In:	Corner Code #
(County) Kochville Township		
1. Public Land Survey	T <u>13</u> NR <u>4E</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MILDRED H. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

SEP 27 11 44 AM '96

RECORDED & FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on August 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-9 Post set by J. Wampler D.S. in 1822.

L.C.R.C. - L. 1, P. 240 by John Martin - fnd 7/8" solid iron bar.
Recorded Surveys: L. 1922, P. 1099; L. 1783, P. 1226; L. 1783, P. 2058; L. 1729, P. 373.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

A-9 Fnd 3/4" iron bar 30" long with pointed bottom.

Recorded Witnesses as follows:

S 45° E 72.79' (72.50' - R to face) to PK nail in SW face of pole.
NE 58.73' (58.20' - R to face) to spike in SE face of corner fence post
S 62.00' to M-9, T13N, R3E.
Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 Replaced 3/4" iron bar with Saginaw County Remonumentation cap on 5/8" rebar 18" long in monument box.

S 45° E 72.79' to PK nail in SW face of pole.
NE 58.73' to spike in SE face of corner fence post.
S 75° E 46.11' to spike in wood guard rail post.
N 50° W 103.65' to NE corner of garage attached to Hse. #7024.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 25 Sept 96

MAY 1 6 1997