

6-30 BLP

SEP 28 3 16 PM '99

For corners in

MILWAUKEE
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

LIBER 2144 PAGE 746

Line 8 Page 18

Register of Deeds Stamp & File Number

<u>Saginaw</u> (County)	Located In: Kochville Twp.	Corner Code # A-12
1. Public Land Survey	T <u>13N</u> R <u>4E</u>	<u>A-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Roger P. Mahoney, in a field survey on 4-6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12 Corner not physically set in original Gov't survey.
 Consumers Power Co. map, 1957 found stone to surface with RR spike.
 Act 132 L1592 P685 shows & witnesses W. 1/4 cor. Sec. 31 but corner is East 1/4 cor. Sec. 36, T.13 N.-R.3 E.
 Spicer notes 1983 found stone set 3/4" pipe over stone on town line & 32.8' North of M-12, T.13 N.-R.3 E. as per Consumers map.
 LCRC L1629 P688 Prevost 1983 same as 1983 Spicer notes.

SURVEY &
 REGISTERED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MAR 09 2000

A-12 Found 3/4" pipe.
 Monument accepted as the best position for the corner.

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 Removed 3/4" pipe found large pointed stone with smaller stones around.
 Removed stones and set 5/8" bar, Saginaw County re-mon cap stamped #24612 and mon box.
 S.42°W. 87.10 top splice NE leg tower (record 87.1 Spicer 1983 & LCRC L1629 P688).
 South 32.89 1" pipe M-12, T.13 N.-R.3 E. (record 32.8 consumers 1957 & Spicer 1983).
 S.35°W. 44.67 new chiseled "+" W. end 48" conc. pipe.
 S.20°E. 43.22 new chiseled "+" E. end 48" conc. pipe.



Signed by Roger P. Mahoney
 Roger P. Mahoney
 Surveyor's Michigan License No. 41105

Date 9-27-99