

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY
 SAGINAW COUNTY REMONUMENTATION 1999 RECORDED & FILED
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SEP 28 3 16 PM '99

For corners in

<u>Saginaw</u> (County)	Located In: <u>Kochville Twp.</u>	Corner Code # <u>B-9</u>
1. Public Land Survey	T <u>13N</u> R <u>4E</u>	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MICHIGAN
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

LIBER 2144 PAGE 745

Liber 8 Page 17

Register of Deeds Stamp & File Number

I, Roger P. Mahoney, in a field survey on 4-6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9	●											
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-9 Post set by D.S. Joseph Wampler 1822.
 Beech 9" N.36 1/2°E. 7 Lks.
 Beech 10" S.10°W. 11 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


B-9 Found 3/4" pipe @ surface, all witnesses indicate the 3/4" pipe position.
 Act 132 L1922 P1099 Ledy 3/4".
 Act 132 L1983 P1762 Ledy 3/4".
 Spicer Eng. notes 1971 found 3/4" pipe.
 Act 132 Martin L1349 P63 1971 3/4" pipe.
 LCRC L1 P240 Martin 1972 3/4" pipe.
 Spicer notes 1973 3/4" pipe.
 SCRC notes 1988 3/4" pipe.

Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9 Replaced 3/4" pipe with 5/8" rod, Saginaw County re-mon cap stamped #24612 & mon box.
 N.25°E. 59.68 SW cor. conc. blk fnd house (59.68 Spicer 1971)(LCRC L1 P240 59.68).
 S.15°E. 88.60 NW cor. conc. blk fnd house (88.58 Spicer 1971)(LCRC L1 P240 88.58).
 S.50°W. 135.28 NW cor. stone chimney (record 135.28 Spicer 1971)(LCRC L1 P240 135.28).
 S.05°W. 57.53 P.K. W. side U.P. (record 56.97 Spicer face pole 1973)(57.00 face SCRC) (record 57.53 L1922 P1099).

SURVEY &
 RECORDED
 MAR 09 2000
 SECTION



Signed by Roger P. Mahoney
 Roger P. Mahoney
 Surveyor's Michigan License No. 41105

Date 9-27-99