

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION 1999 RECORDED & FILED
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

6-30 BIP
 For corners in

SEP 28 3 16 PM '99

MICHIGAN
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

LIBER 2144 PAGE 742

Liber 8 Page 14

Register of Deeds Stamp & File Number

<u>Saginaw</u> (County)	Located In: <u>Kochville Twp.</u>	Corner Code # <u>C-8</u>
1. Public Land Survey	T <u>13N</u> R <u>4E</u>	<u>C-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Roger P. Mahoney, in a field survey on 8-26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19	●	20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-8 Post set by D.S. Joseph Wampler, 1822.
 Ash 20" N.73 1/2°E. 18 Lks.
 Sugar 10" S.86°W. 28 Lks.

SURVEY &
 SECTION
 MAR 09 2000

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SECTION

C-8 Found 3/4" pipe.
 Spicer Act 132 L1402 P764, 1972 nail found; SW 28.97 face T. pole; E 59.04 face P. pole.
 Spicer notes 1973, nail found; SW 28.97 face T. pole; E 59.04 face P. pole.
 LCRC L2 P111, Martin 1973, nail; SW 28.97 face T. pole; E 59.04 face P. pole.
 Spicer notes 1973, set 3/4" in place of nail; SW 28.97 face T. pole; E 59.04 face P. pole.
 Spicer notes 1974, found 3/4" pipe; SW 28.97 face T. pole; E 59.04 face P. pole.
 SCRC notes 1977, found 3/4" pipe; East 59.40 nail & cap S. side P. pole; N.45°E. 167.18 SW cor shed.

Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 Replace 3/4" pipe with 5/8" rod, Saginaw County re-mon cap stamped #24612 & mon box.
 East 59.52 40 N nail N side P. pole (R 59.04 face).
 N.50°E. 167.18 S.W. cor. metal pole bldg. (R 167.18).
 S.70°E. 125.39 N.W. cor. brick house #7520.
 S.10°E. 169.91 set N & T N.W. side 20" Oak.

Signed by Roger P. Mahoney
 Roger P. Mahoney
 Surveyor's Michigan License No. 41105

Date 9-27-99

