

APPROVED BY PEER GROUP **SAGINAW COUNTY REMONUMENTATION 1999**
P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE
SAGINAW COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED & FILED

SEP 20 3 16 PM '99

MICHIGAN
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

LIBER 2144 PAGE 748

Liber 8 Page 20
 Register of Deeds Stamp & File Number

For corners in _____

_____ Saginaw _____ Located In: _____ Corner Code # _____
 (County) Kochville Twp.

1. Public Land Survey T 13N R 4E _____ C-9
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Roger P. Mahoney, in a field survey on 4-6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-9 Post set by D.S. Joseph Wampler, 1822.
 Beech 10" N.60 1/2°E. 6 Lks.
 Ironwood 9" N.81°W. 16 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 Found 3/4" pipe at bit. surface.
 Spicer notes 1973 fnd. 3/4" pipe.
 LCRC L3 P79 Martin 1974 3/4" pipe.
 LCRC L4 P24 McGinnis 1977 3/4" pipe.
 SCRC notes 1988 3/4" pipe.
 Act 132 L1983 P1762 Ledy, 1993 3/4" pipe.

Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Replaced 3/4" pipe with 5/8" bar, Saginaw County re-mon cap stamped #24612 & mon box.
 N.70°E. 66.04 nail & tag SE Side P. pole (rec LCRC L & P24, 66.0)(SCRC, 1988 66.00)
 (Act 132 L1983 P1762, 66.00).
 S.50°E. 80.60 nail & tag NE side P. pole (rec 80.15 face Spicer 1973)(LCRC L3 P79, 80.15)
 (SCRC, 1988, 80.63).
 S.35°W. 57.00 nail & tag in SE side P. pole (rec 57.2 LCRC L4 P24)(SCRC, 1988, 57.15)
 (Act 132 L1983 P1762, 57.00).
 N.15°E. 200.84 top center hydrant.

SURVEY &
 RE-MONUMENTATION
 MAR 09 2000
 SECTION



Signed by Roger P. Mahoney
 Roger P. Mahoney
 Surveyor's Michigan License No. 41105

Date 9-21-99