

APPROVED BY PEER GROUP  
 P.A. 345 OF 1990  
 SAGINAW COUNTY  
**SAGINAW COUNTY REMONUMENTATION 1999 RECORDED & FILED**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

6-30 *[Signature]*  
 For corners in

SEP 28 3 16 PM '99

MICHIGAN  
 REGISTER OF DEEDS  
 SAGINAW COUNTY MICH.

LIBER 2144 PAGE 740

*Liber 8 Page 12*

Register of Deeds Stamp & File Number

Saginaw (County) Located In: Kochville Twp. Corner Code #

1. Public Land Survey T 13N R 4E C-11  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Roger P. Mahoney, in a field survey on 4-6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11 Post set by D.S. Joseph Wampler, 1822.  
 Elm 24° S.78°E. 10 Lks.  
 Sugar 14° N.65°W. 7 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Found 1/2" rod over 3/4" pipe & large stone.  
 Spicer notes 1952 large stone, 3/4" pipe over.  
 Spicer notes 1967 1/2" rod.  
 LCRC L1 P120 ? iron no distance on witnesses.  
 Act 132 L1571 P172 Schaefer 1972 1/2" rod.  
 Spicer notes 1978 1/2" iron.  
 LCRC L4 P143, Prevost, 1978 1/2" rod.  
 SCRC notes 1990 1/2" rod.

Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Replaced 1/2" rod, 3/4" pipe & stone with 5/8" bar, Sag. Co. re-mon cap stamped #24612 & mon box.  
 S.30°E. 52.82 top center hydrant (Spicer 1978, 52.82).  
 N.65°E. 54.92 nail & tag NW side P. pole (rec 54.62 face Spicer 1967)(54.86 L1571 P172)(LCRC L4 P143 54.62).  
 N.45°W.35.96 nail & tag SW side P. pole (rec 35.55 face Spicer 1967)(35.97 L1571 P172)(LCRC L4 P143, 35.55)  
 (1990 SCRC 35.95).  
 S.55°W. 37.05 top ctr. tel. ped. (SCRC 1990, 36.5 face)(Spicer 1978, 36.74).  
 N.40°W. 39.05 ctr. iron St. sign post (rec 39.10 Spicer 1952).

SURVEY &  
 RECORDED  
 MAR 09 2000  
 SECTION

Signed by Roger P. Mahoney  
 Roger P. Mahoney

Date 9-27-99

Surveyor's Michigan License No. 41105

