

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY
SAGINAW COUNTY REMONUMENTATION 1999
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED & FILED

SEP 28 3 16 PM '99

MICHAEL J. ...
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2144 PAGE 739

Lib 8 Page 11

Register of Deeds Stamp & File Number

For corners in _____
Saginaw _____
(County)

Located In: _____
Kochville Twp.

Corner Code # _____

1. Public Land Survey T 13N R 4E Corner Code # C-12
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Roger P. Mahoney, in a field survey on 4-6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-12 Post set by D.S. Joseph Wampler, 1822.
Beech 7" S.69 1/2°E., 10 Lks.
Sugar 10" N.52°W., 20 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 Found 3/4" pipe @ Bit-surf.
Spicer notes 1956 set nail.
LCRC L2 P241 1974 set & record 3/4" pipe, same wit's as nail 1956.
Act 132 L1571 P172, Schaefer 3/4" pipe.
Act 132 L1883 P330, Prevost 3/4" pipe.
Spicer notes 1993 3/4" pipe.

Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 Replaced 3/4" pipe with 5/8" rod, Sag. Co. re-mon cap stamped #24612 & mon box.
North 13.10 S legs of tower line to East. (Rec 13.1 Spicer 1956)(13.1 L2 P241).
N.85°E. 48.19 nail & tag N face T. pole. (rec 49.3 Spicer 1956)(49.3 L2 P241)(49.12 L1571 P172)
(48.86 face L1883 P330).
S.10°E. 108.10 ctr top hyd (Rec 108.10 L1883 P330).
S.45°E. 149.27 SW leg tower @ splice.

SURVEY &
REGISTERED PROFESSIONAL SURVEYOR

MAR 09 2000

SECTION

Signed by Roger P. Mahoney
Roger P. Mahoney

Date 9-2-99 NO. 41105

Surveyor's Michigan License No. 41105

